


IF IN DOUBT ASK



MARTIN-DECKER
A Division of Varco (U.K.) Ltd

- NOTES**
1. Wiper control boxes are fitted with wash control valves.
 2. Air actuated valves fitted in water line have a operating pressure of 80 psi (5.5 Bar).
 3. Air/Filter regulator fitted in main air line to be pre-set at 80 psi (5.5 Bar).
 4. Deck penetrations for Air, Water and Drainage pipes to be provided by others.
 5. Water pipes located in floor void to be heat-traced and thermally insulated.
 6. All pipework to be site run and supported on proprietary pipe clamps.
 7. Electrical heat trace on water line by Consafe, 240V 50/60Hz power supply required, source by others refer to Drawing No. PO-162-D-0002 (AB/2191-3- 3001).

- LEGEND**
- WATER LINE
 - AIR LINE
 - ISOLATION VALVE
 - WATER & CLEANING FLUID PROPORTIONAL FEEDER
 - PRESSURE REGULATOR (0-4 - 10 BAR)
 - MICROSTRAINER
 - AIR FILTER
 - AIR ACTUATED VALVE

AS SUPPLIED

Sellers statement:
This document accurately
represents the as supplied
condition of the work

Seller's Authorised Signature: *B. V. [Signature]* Date: 30.4.92

- COMPANY RETURN CODES**
- ☒ 1. Accepted - As Supplied
 - ☐ 2. Accepted - No Comments
 - ☐ 3. Qualified Acceptance - Minor Comments. Review & Resubmit as 'As Supplied' Work May Proceed
 - ☐ 4. Qualified Acceptance - Minor Comments. Review & Resubmit To Obtain Code 2 Work May Proceed
 - ☐ 5. Qualified Acceptance - Major Comments. Review & Resubmit To Obtain Code 2 Work May Proceed
 - ☐ 6. Rejected - Review & Resubmit Immediately Work May Not Proceed In The Affected Areas
 - ☐ 7. Review Not Required

AMERADA HESS LIMITED
SCOTT FIELD DEVELOPMENT

Package Desc	DRILLING INSTRUMENTATION AND DRILLERS CABIN
Equip Nos	
SDRS Codes	D-01
Module	
Purchase Order No	PO 162
Document No	0 0 0 0 1 0 4
Rev	

ISSUE	REV	DATE	BY	DESCRIPTION	DATE	CHKD
4	6-3	DR		AS SUPPLIED	2/4	
3	29-8	AWC		ISSUED FOR CONSTRUCTION	29/8	
1	11-6	AWC		ISSUED FOR APPROVAL	11/6	
Q	31-1	SC		ISSUED FOR INFORMATION	31/1	

Consafe Engineering (UK) Ltd

CLIENT: MARTIN DECKER
PROJECT: DRILLING INSTRUMENTATION AND DRILLERS CABIN

DRAWN BY	DATE	TITLE
L. Dye	31.1.91	PNEUMATIC WIPER SYSTEM PIPING & INSTRUMENT DIAGRAM
CHECKED BY	DATE	
M. SOM	31.1.91	
APPROVED BY	DATE	
B. V. [Signature]	31.1.91	
FILE No		
SCALE		
NTS		A1
DRG No		AB/ 2191-4-4000